BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to : **Original / Duplicate**

Name of Work: Supply and installation of CCTV cameras at selected points in ward no 12 - Kodigehalli

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	16.00	Supplying ,Installartion,Commisoning and Testing CP Plus 3MP ,Meters ip bullet camera,1/3" 3MP PS CMOS image sensor 25fps@3MP ,25/30fps@1080P , H.264,H.264H ,H.264B,MJPEG dual- codec encording DWDR configure(CR) 3DNR,ROI , AWB AGC,BLC , HLC 3.6mm fixed lens (6mm optional),IR Range of 50Mtr IP67 6' , perd,PoE Mobile software iCMOB, CMS Software :KVMS Pro ,vOptimus Pro inclusive of all Taxes , transportation charges as per the direction of Engineer incharge .	No	22160.00	Rupees Twenty Two Thousand One Hundred Sixty Only
2	1.00	Supplying ,Installation,Commisioning and Testing CP PLUS 32 Ch.H.265,4K Network Vedeo Recorder Up to 32 channel IP Camera,input H265/H 264 dual codec decording up to 8Mp resolution preview and playback Max 200Mbps incoming bandwidth support 4SATA HDDs upto 24 TB ,2USB(1USB3.0)HDMI/VGA simaltaneous vedeooutpu support multy band network cameras ONVIF Version 2.4 conformance mobile software iCMOB ,gCMOB inclusive of all taxes transportation charges as per the direction of Engineer incharge .	No	65892.00	Rupees Sixty Five Thousand Eight Hundred Ninety Two Only
3	1.00	Supplying ,Installation,Commisioning and Testing Netgear Ready NAS 4bay Diskless Network Attached Storage for personal Cloud by Netgear inclusive of all taxes transportation charges as per the direction of Engineer incharge	No	256420.00	Rupees Two Hundred Fifty Six Thousand Four Hundred Twenty Only
4	1.00	Providing and supplying NAS Hard disk 6 TB inclusive of all taxes transportation charges as per the direction of Engineer incharge .	No	23850.00	Rupees Twenty Three Thousand Eight Hundred
5	1.00	Supplying ,Installation,Commisioning and Testing D-Link 24-Port Gigabite Switch with 4 combo SFP Ports inclusive of all taxes transportation charges as per the direction of Engineer incharge .	No	34300.00	Rupees Thirty Four Thousand Three Hundred Only
6	1.00	Supplying ,Installation,Commisioning and Testing D-Link 8-Port Gigabite Switch with 2 combo SFP Ports inclusive of all taxes transportation charges as per the direction of Engineer incharge .	No.	27500.00	Rupees Twenty Seven Thousand Five Hundred Only
7	7.00	Providing and supplying CATS out door-305 Mtr cable Box inclusive of all taxes transportation charges as per the direction of Engineer incharge .	No.	63250.00	Rupees Sixty Three Thousand Two Hundred Fifty
8	1.00	Providing and fixing Media converter Giga Dlink inclusive of all taxes transportation charges as per the direction of Engineer incharge .	No.	11200.00	Rupees Eleven Thousand Two Hundred Only
9	8.00	Providing Cctv MS poles with camera fixing brackets 5 to 6 Mtr Height Box inclusive of all taxes transportation charges as per the direction of Engineer incharge .	No.	23500.00	Rupees Twenty Three Thousand Five Hundred Only

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
10	8.00	Providing and fixing MS Boxes to poles with rust proof powder coating Box inclusive of all taxes transportation charges as per the direction of Engineer incharge .	No	8500.00	Rupees Eight Thousand Five Hundred Only
11	8.00	Providing and fixing electrical works for Boxes for power supply PVC Boards with three pin sockets and switches with protection MCB and cabling to street light electrical poles as per the direction of Engineer incharge	No	7500.00	Rupees Seven Thousand Five Hundred Only
12	12.00	Providing Internet charges connecting CCTV with IP Based for one month	No	3000.00	Rupees Three Thousand Only
13	3.00	Providing and fixing SFP-LX-SM GIGA Module Box inclusive of all taxes transportation charges as per the direction of Engineer incharge .	No	6000.00	Rupees Six Thousand Only
14	3.00	Providing and fixing fiber optic PATCH Chords Box inclusive of all taxes transportation charges as per the direction of Engineer incharge .	No	2200.00	Rupees Two Thousand Two Hundred Only
15	2.00	Supplying ,Installation,Commisioning and Testing UPS 2 KVA with 2 Bateries Box inclusive all taxes transportation charges as per the direction of Engineer incharge .	No	64400.00	Rupees Sixty Four Thousand Four Hundred Only
16	8.00	Erecting of pole ,The pole shall be erected and cement concrete work (1:2:4) including earthwork excavation and refilling of planting depth of the pole to the ground level and the coping CC shall be upto 0.6Mtrabove ground level as per IS 2713-7.1 Erection of light duty pole on footpath 7.5m as per IS 410 Sp 5 charges as per the direction of Engineer incharge .	No	6300.00	Rupees Six Thousand Three Hundred Only
17	16.00	Providing and fixing HDMI cables 10Mtrs inclusive of all taxes transportation charges as per the direction of Engineer incharge .	No	6200.00	Rupees Six Thousand Two Hundred Only
18	3.00	Supplying ,Installation,Commisioning and Testing Vedeo Manager Application Software Manager for display and Management of Camera on vedeo display Box inclusive of all taxes transportation charges as per the direction of Engineer incharge .	No	33500.00	Rupees Thirty Three Thousand Five Hundred Only
19	4.00	Supplying ,Installation,Commisioning and Testing server rack 15u box inclusive of all taxes transportation charges as per the direction of Engineer incharge .	No	34500.00	Rupees Thirty Four Thousand Five Hundred Only

HOTJ Approved

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಕಚೇರಿ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

Note:

1 Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)

2 Unit rates and prices shall be quoted by the Tender in Indian rupees.

3 Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a)

4 Where there is a discrepancy between the unit rate and the line item total resulting from multyplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))